

ADDENDUM TO THE PROJECT OF THE e_9 BEAM LAYOUT

The layout described in the NOTE MPS/MU/EP 70-3 (20.2.1970) has not altered in principle, but in some detail due to requirements which came up in the mean time.

- 1) The optics proposed for the main beam as well as for the branches is altered slightly as shown in Fig. 1.
- 2) Magnets with larger vertical apertures are used in the South branch.
- 3) The beam line of the North branch is modified. The Hyperon beam line is deflected to the North with respect to the e_9 branch. Two different beam lines of the North branch are anticipated according to two different target positions for the Hyperon branch. Details are given in the Appendix.
- 4) We assume, after discussions, that ss 64 is not used for the electrostatic septum; if this is not so, then this layout has to be taken into consideration.
- 5) We assume further, no drastic changes of the present emittance of the slow ejected beam, in particular we assume the present ejection scheme with the use of the septum lens in ss 63 during 1971.

The proposed layout is shown on the attached plan. The installation of vacuum tubes, chambers and branches are given in the NOTE/EP 70-4 (4.3.1970). The altered layout anticipates to stop the vacuum of the machine with the SEC 1. In the South branch two additional chambers are required for the magnets MNP 08. In the North branch a chamber for M 200 in front of the target has to be provided.

Table 1 summarizes the elements required for the main beam and the two branches as well as observation and monitor stations.

The targets in both branches are special targets, delivered and mounted by the experimental teams. As target monitor we envisage a telescope directed at 90° to the b_{19} target (in front of a special magnet in the South branch) and a charge measurement of the insulated target y_1 (mounted inside a 2 m magnet) .

D. Dumollard
L. Hoffmann

Distribution :

V. Agoritsas	G. Petrucci
J. Allaby	J. Robert
Y. Baconnier	W. Richter
G. Backenstoss	V. Soergel
P. Coet	P.H. Standley
A. Colombo	Ch. Steinbach
L. Danloy	J. Steinberger
P. Darriulat	M. van Rooy
D. Dekkers	F. Vriens
L. Dick	
J.Y. Freeman	
M. Ferro-Luzzi	
H. Filthuth	
P. Forrat	
J.-M. Gaillard	
J. Geibel	
K. Geobel	
B.D. Hyams	
R. Jacquin	
C. Johnson	
K. Kleinknecht	
J. Léault	
J.H.B. Madsen	
O. Martin	
R. Meunier	
G.L. Munday	
G. Plass	

A P P E N D I X

Fig. 2 shows the possible changes of the production angles for the y_1 beam line 111 mr deflected to the North with respect to the e_{9n} branch. The central line corresponds to a production angle of 30 mr. In this case the y_1 target is mounted 50 cm inside (iron length) M 200 , as shown on the attached layout. We plan a second beam line of the e_{9n} branch with an angle of 143 mr with respect to the unaltered y_1 line. In this case the target y_1 is positioned at the entrance of the 2 m magnet.

T A B L E II. BEAM TRANSPORT ELEMENTS

Main beam line	South branch	North branch	Mrad	Mrad
1 MNPA (H)	2 MNP 18	1 MNP 23	2 x (-13)	+49
2 Q 120	1 MV (spec.)	1 MV (spec.)		
1 MNPA (V)	1 MNP 19	1 MC 200	-28	+31.77
1 M 211	2 MNP 08	1 MNPA (V)	2 x (-13)	
1 Q 600	1 Q 050	1 Q 100		
1 Septum (I)	2 ME 150	2 Q 200	2 x (-37)	
1 Q 600	2 Q 120	1 MNPA (V)		
1 MTC 06 (H)	2 MNPA (V/H)	1 M 100		(Δ)
1 Q 200		1 M 200		+19.12 (Δ)
1 Septum (II)				
2 Q 120				
2 MNPA (V/H)				

Δ) used for changes of the production angle for both beam lines (see appendix)

$\Delta\Delta$) for 111 mr between e_{9n} and y_1 (30 mr production angle)

II. BEAM OBSERVATION AND MONITORS

Main beam line	South branch	North branch
<p>a) <u>Station for TV observations</u></p> <p>TV 2 screen box to be modified.</p> <p>TV 4 screen box connected to $\phi 20$ cm vac. tube. Screen vert. ≈ 15 cm hor. ≈ 6 cm.</p> <p>TV 5 screen box connected to $\phi 20$ cm vac. tube. Screens standard size.</p> <p>TV 6 screen box connected to $\phi 20$ cm vac. tube. Screen $\phi 15$ cm.</p> <p>TV 7 target station (as present)</p>	<p>TV 8 screen box connected to $\phi 20$ cm tube. Screen ϕ standard size.</p> <p>TV 9 screens in air (standard system.)</p>	<p>TV 10 as station 8</p> <p>TV 11 as station 9</p>
<p>b) <u>Monitor stations</u></p> <p>SEC 1 (SEC+Rings) Ring (foils $\phi_e = 12$ cm, $\phi_i = 7$ cm) in construction</p> <p>TOPOSCOP (vert.) in construction</p> <p>SEC 2 (SEC 20 + rings)</p>	<p>SEC 3 in construction ($\phi 12$ cm, 10 foils + 10 ring foils).</p>	<p>SEC 4 in construction as SEC 3</p>
<p>c) <u>Targets</u></p> <p>at station TV 7 as present</p>	<p>y_1 target (special) and b_{19} target (special) delivered and mounted by experimental teams.</p>	






Fig.1





Fig.2

Change of production angle for y_1

Example for the y_1 line with a mean angle of 111 mr with respect to the incident protons (target position 50 cm inside the M 200.)



e9
e9n , e9s
PROJECT 70.290.0 MPS

ELECT S 5
3740