

EUROPEAN ORGANIZATION FOR NUCLEAR RESEARCH
CERN - ACCELERATORS AND TECHNOLOGY SECTOR



CERN/ATS 2010-178

**COMMISSIONING AND FIRST OPERATION
OF THE LARGE HADRON COLLIDER (LHC)**

Ph. Lebrun
CERN, Geneva, Switzerland

Abstract

After some fifteen years of construction, the Large Hadron Collider (LHC) was commissioned at CERN, the European Organization for Nuclear Research in 2008. This high-energy particle accelerator of 26.7 km circumference – the largest scientific instrument ever built – brings into collision intense beams of protons and ions to probe the structure of matter and study the forces acting on its elementary components at the TeV scale, an order of magnitude higher than the previous state-of-the-art. To guide and focus its particle beams, the LHC uses several thousands high-field superconducting magnets operating in superfluid helium at 1.9 K. The project therefore constitutes a technological feat: all its components were developed, industrialized and series produced by industrial companies according to demanding specifications. Started as a CERN undertaking – by decision of the CERN Council and its twenty European member states – the project soon became global with special contributions from Canada, India, Japan, Russia and the United States of America. After recalling the technical stakes of the project, we present the main results from the construction and commissioning phases and from the first beam operation. We also summarize the detailed investigations conducted after the incident of 19 September 2008, to analyze its causes and draw conclusions for repair and consolidation. We finally report on the restart of the machine in 2009 and on its first operation for physics.

CERN-ATS-2010-178
01/08/2010



Invited plenary lecture at the 23rd International Cryogenic Engineering Conference (ICEC 23)
Wroclaw, Poland, 19-23 July 2010

Geneva, Switzerland

August 2010

Commissioning and First Operation of the Large Hadron Collider (LHC)

Lebrun, Ph.

DG Unit, CERN, 1211 Geneva 23, Switzerland

After some fifteen years of construction, the Large Hadron Collider (LHC) was commissioned at CERN, the European Organization for Nuclear Research in 2008. This high-energy particle accelerator of 26.7 km circumference – the largest scientific instrument ever built – brings into collision intense beams of protons and ions to probe the structure of matter and study the forces acting on its elementary components at the TeV scale, an order of magnitude higher than the previous state-of-the-art. To guide and focus its particle beams, the LHC uses several thousands high-field superconducting magnets operating in superfluid helium at 1.9 K. The project therefore constitutes a technological feat: all its components were developed, industrialized and series produced by industrial companies according to demanding specifications. Started as a CERN undertaking – by decision of the CERN Council and its twenty European member states – the project soon became global with special contributions from Canada, India, Japan, Russia and the United States of America. After recalling the technical stakes of the project, we present the main results from the construction and commissioning phases and from the first beam operation. We also summarize the detailed investigations conducted after the incident of 19 September 2008, to analyze its causes and draw conclusions for repair and consolidation. We finally report on the restart of the machine in 2009 and on its first operation for physics.

INTRODUCTION

The Large Hadron Collider (LHC) [1] is now currently delivering colliding beams of protons at the unprecedented center-of-mass energy of 7 TeV, to the six particle physics experiments located in four underground caverns around its 26.7 km circumference (Figure 1). This is both the end of a long story of engineering design, targeted R&D in the key technologies of superconducting magnets and cryogenics, industrialization, construction, installation and commissioning, and the beginning of a twenty-year operation phase for physics at the energy frontier (Table 1). In the following, we recall the essential features of the project [2] and describe the cryogenic aspects of its commissioning and first operation.




Figure 1 The Large Hadron Collider: (a) footprint in the Geneva basin; (b) inside the machine tunnel

Table 1 Time line of LHC project

Preliminary conceptual studies	1984
Start of structured R&D program	1990
Project approval by the CERN Council	1994
Industrialization of series component production	1996-1999
“Déclaration d’Utilité Publique” and start of civil works	1998
Adjudication of main procurement contracts	1998-2001
Start of installation of services in tunnel	2003
Cryomagnet installation in tunnel	2005-2007
Cooldown and functional tests of first sector	2007
First commissioning with beam	2008
Repair, consolidation and re-commissioning	2009
Operation for physics	2010-2030

In order to bend, focus and bring into collision intense beams of protons and ions at center-of-mass energy of up to 14 TeV, the LHC uses several thousand high-field superconducting magnets, using Nb-Ti superconductors operating at 1.9 K in superfluid helium [3]. The 1232 dipoles (nominal field 8.33 T) and 392 main quadrupoles (nominal gradient 223 T/m), occupy most of the circumference of the machine and constitute the largest fraction of its 37’000 ton cold mass. In view of the size of the project, all such components had to be produced by industry according to CERN specifications [4]. Following quality assurance procedures applied at room temperature on the manufacturers’ premises, the superconducting magnets were assembled into their cryostats by industry on the CERN site. A major challenge was to design, series manufacture and assemble helium II cryostats with demanding thermal budget (heat inleak on

the cold mass of 0.2 W/m at 1.9 K [5]) using industrial methods applied by non-specialized personnel, so as to contain costs while achieving reliable and robust performance [6]. To this end, the cryostats feature *inter alia*, an all-welded helium enclosure made of austenitic stainless steel, a gaseous-helium cooled thermal shield of extruded aluminium with built-in cooling channel, pre-fabricated blankets of multi-layer insulation around the magnet cold mass and the thermal shield, and low heat in-leak, high-strength support posts made of non-metallic composite material with heat intercepts [7]. Following assembly, each cryo-magnet was connected to a cryogenic test bench, where it underwent its first cool-down to operating temperature, leak-tightness and electrical insulation tests, instrumentation checks, powering up to resistive transition, training to 9 T and, for a sample of the total number, detailed magnetic measurements [8]. Performing these tests required considerable resources in terms of cryogenic infrastructure [9], and sustained round-the-clock operation for several years. They however proved essential to clear the cryo-magnets for installation in the tunnel, as they permitted to detect a few defects which had not been intercepted by the quality assurance checks performed at room temperature.

The cryo-magnets were then transported underground and pre-aligned to their final positions in the tunnel. Electrical and cryogenic interconnections then proceeded [10], from cryo-magnet to cryo-magnet as well as to the cryogenic distribution line previously installed in the tunnel [11], to constitute 3 km long sectors electrically powered in series from current feed boxes located at either end, through current leads using high-temperature superconductors [12]. Global leak and pressure tests finally validated the completed sectors for cryogenic operation.

MAIN FEATURES OF LHC CRYOGENICS

In parallel with the production and reception testing of cryo-magnets, the components of the LHC cryogenic system [13] were procured, installed and commissioned. The basic layout is shown in Figure 2: five of the eight access points to the tunnel are cryogenic “islands”, housing refrigeration and ancillary equipment serving the adjacent underground sectors. This configuration provides partial redundancy by allowing any of the two plants in one island to serve either adjacent sector, through an interconnection valve box. A standard island thus contains two 4.5 K cryogenic plants and two 1.8 K refrigeration units with their compressor stations, the interconnection box to the tunnel, six 250 m³ and ten 75 m³ gaseous helium storage vessels at 2 MPa [14], two 50'000 l liquid nitrogen vessels, piping and cryogenic lines interconnecting the different components, and a local control room.

The 4.5 K cryogenic plants, of 18 kW equivalent refrigeration capacity at 4.5 K, provide mixed refrigeration and liquefaction duties. Four of these plants were recovered from the previous LEP project and suitably upgraded [15], while the other four were procured from industry upon functional-and-interface specification [16]. All plants deliver the specified refrigeration duties with high thermodynamic efficiency, showing COP of 220 to 240 W/W at nominal capacity [17].

The 1.8 K refrigeration units provide 2.4 kW each [18] using three or four stages of hydrodynamic cold compressors, with the final compression performed at room temperature by sub-atmospheric screw compressors. The cold compressors feature axial-centrifugal impellers rotating at speeds up to 800 Hz on active magnetic bearings, thus achieving high efficiency over a dynamic range of 3:1 [19]. The

combination in series of cold hydrodynamic and warm volumetric compressors, as well as the use of elaborate control strategies, yield good compliance to flow transients while ensuring COP of about 900 W/W for the 1.8 K refrigeration units at nominal capacity [20].




Figure 2 Simplified map of the LHC and architecture of the cryogenic system

Cryogenic instrumentation [2] matches the size and technical demands of the project, with *inter alia*, 4500 thermometers covering the range 1.6-300 K with precision up to 10 mK at the low-temperature end, and radiation-tolerant electronics. The control system is based on distributed PLC interfaced to equipment via field buses, and communicating via Ethernet to operator stations using a common SCADA protocol [21]: it simultaneously manages 4700 analog control loops.

FIRST COOLDOWN, FIRST POWERING, FIRST BEAMS

In November 2007, the first sector was cooled down to operating temperature [22, 23]. A prerequisite was to flush all cryogenic circuits with high flow of gaseous helium at room temperature from the refrigeration compressors used as circulators, with periodic removal of filters protecting the sensitive components. This procedure, systematically applied to each sector after any intervention, permitted to collect dust, debris of insulation material and metal filings from the magnets, as well as a few unexpected objects resulting from the installation field work. Controlled cooldown to about 100 K of a 4635 ton sector is achieved by forced circulation through the magnets of gaseous helium, pre-cooled at the rate of up to 600 kW by vaporization of liquid nitrogen at ground level. Thus a complete cooldown of the LHC uses some 10'000 ton liquid nitrogen, which have to be brought on site in a coordinated way by 500 semi-trailer trucks. The final cooldown and liquid helium fill of the sector is performed with the turbines of the 4.5 K cryogenic plant, after which the 1.8 K units are started to progressively subcool the helium in the magnets down to the operating temperature of 1.9 K. After tuning of the cryogenic controls for the steady operation of the sector,

the heat loads were measured and the different magnet circuits powered [24]. Cooldown in turn of the seven remaining sectors was performed in the spring and early summer of 2008 (Figure 3).




Figure 3 First cooldown of the LHC sectors and first beams in the machine

The combination of static pressurized and flowing saturated helium II in the magnet cooling scheme [13] confirmed its efficiency for extracting the heat loads under minute temperature differences, maintaining excellent temperature homogeneity along complete sectors (Figure 4), controlling temperature stability during current ramps and recovering from magnet resistive transitions. In spite of the long heat transport distances, the scheme achieves high exergetic efficiency thanks to the optimal use of the thermophysical properties of helium II and the absence of circulator pumps [25].




Figure 4 Measured temperature profile along a sector of the LHC; the sector is cooled from Point 4

Measurement of the steady-state heat in-leaks on different sectors show values well within the thermal budget [26] both for the magnet cryostats [27] and the cryogenic distribution lines, thus confirming *a posteriori* the methodology for sizing the cryogenic plants and the assessment of design margins [28]. All these measurements – some of them incredibly precise on such an industrial-size system – also provided a validation of the design choices and technical implementation of the LHC cryogenic instrumentation [29], in particular the calibration of thermometers [30].

In parallel with the main magnets discussed above, all other cryogenic sectors of the ring, including long straight sections at the end of the arcs [31] and low-beta insertions around the collision points [32] were also commissioned. With all accelerator systems operational – the main magnet circuits having been commissioned only up to 7 kA out of the nominal 11.85 kA – the first beams were successfully injected at 450 GeV and circulated around the LHC on 10 September 2008.

THE 19 SEPTEMBER 2008 INCIDENT

While completing commissioning of the dipole magnet circuit of sector 3-4, an electrical arc occurred at the interconnection between two magnets when the current ramp reached 8.7 kA. This was traced back to the presence of an abnormal, undetected resistance of 220 n Ω in the electrical interconnect, and of a bad contact between the superconducting cable and the copper stabilizer, the combination of which led to heat dissipation and fast thermal runaway. Although not substantiated by the quality assurance documents, it is likely that the occurrence of these two defects stemmed from a single flaw in the soldering of the interconnection. Electrical detection systems reacted as expected, triggering “fast” discharge of the 595 MJ energy inductively stored in the circuit, with an initial time constant of 100 s. Meanwhile, the resulting electrical arc, already dissipating several MW after only one second, punctured the helium and beam vacuum enclosures. The sudden discharge of helium from the magnet cold mass into the vacuum enclosure occurred at a peak rate of 20 kg/s, an order of magnitude above the sizing conditions of the relief devices on the cryostat vacuum vessel. As a consequence, the pressure in the vacuum enclosure rose to about 0.8 MPa, well above the design value of 0.15 MPa. The resulting axial pressure forces on the vacuum barriers went up to 560 kN, displacing the magnets from their supports and breaking the ground anchors. As a consequence, several other interconnections were damaged, creating secondary arcs. The inrush of helium into the beam vacuum also carried contamination by soot and chips of torn multilayer insulation to large distances into the beam pipes. About 2 t of helium were eventually released to the tunnel in the first two minutes, creating ODH conditions for several hours. A detailed analysis of the incident, including lessons drawn and recommendations, can be found in reference [33].

REPAIR, CONSOLIDATION AND RESTART

The incident damaged some 750 m of machine, requiring the removal of 53 cryo-magnets and their replacement by available spares between January and April 2009. *In situ* inspection and cleaning of the beam pipes were performed on the remaining length of the sector. The maximum credible incident for

helium discharge from the cold mass was redefined [34] and 900 additional, larger pressure relief ports were fitted to the vacuum enclosure. Ground anchors were reinforced, and new longitudinal restraints were fitted to the cryostats housing the insulation vacuum barriers. A new magnet protection system monitoring the interconnections with a detection sensitivity increased by three orders of magnitude was implemented, requiring the pulling of some 250 km new cables connecting 6500 new electronic crates to the magnet terminals. High-current magnet interconnections in the other sectors of the machine were checked by calorimetric [26] and electrical methods, revealing potentially risky operation at nominal level. Following cooldown and re-commissioning of the sectors, it was therefore decided to restart the LHC at maximum center-of-mass energy of 7 TeV and operate it for physics in the period 2010-2011. A long shutdown in 2012 will then be devoted to the final consolidation to allow operation at full energy from 2013 onwards. In spite of some difficulties inherent to the first operation of such a complex system, the LHC is now running smoothly and producing collisions for physics, with an overall cryogenic availability of about 90 % [35].

REFERENCES

1. Evans, L. (editor), The Large Hadron Collider: a marvel of technology, EPFL/CRC Press, Lausanne/Boca Raton (2009)
2. LHC Design Report, Volume I, The LHC Main Ring, CERN-2004-003 (2004)
3. Rossi, L., The Large Hadron Collider and the role of superconductivity in one of the largest scientific enterprises, IEEE Trans. Appl. Superconductivity (2007) 17 1005-1014
4. Lebrun, Ph., Industrial technology for unprecedented energy and luminosity: the Large Hadron Collider, EPAC9 Lucerne, JACoW (2004) 6-10
5. Lebrun, Ph., Design of a cryostat for superconducting accelerator magnets : the LHC main dipole case, in Proceedings of the CERN Accelerator School on Superconductivity and Cryogenics for Accelerators and Detectors, 8-17 May 2002, Erice, CERN-2004-008 (2004) 348-361
6. Poncet, A. & Parma, V., Series-produced He II cryostats for the LHC magnets: technical choices, industrialization, costs, Advances in Cryogenic Engineering, AIP985 (2008) 53A 739-753
7. Poncet, A., Struik, M., Trigo, J. & Parma, V., The LHC cryomagnet supports in glass-fiber reinforced epoxy: a large-scale industrial production with high reproducibility in performance, Advances in Cryogenic Engineering, AIP986 (2008) 54 211-218
8. De Rijk, G. *et al.*, Performance of LHC Main Dipoles for Beam Operation, EPAC10 Edinburgh, JACoW (2006) 2610-2612
9. Axensalva, J., Benda, V., Herblin, L., Lamboy, J.P, Tovar-Gonzalez, A. & Vullierme, B., Cryogenic Infrastructure for Testing of LHC Series Superconducting Magnets, ICEC20 Beijing, Elsevier (2005) 1015-1018
10. Fessia, P. *et al.*, The LHC continuous cryostat interconnections: the organization of a logistically complex worksite requiring strict quality standards and high output, EPAC11 Genoa, JACoW (2008) 2428-2430
11. Barbier, B. *et al.*, Manufacturing and installation of the compound cryogenic distribution line for the Large Hadron Collider, ICEC21 Prague, Icaris (2006) 31-34
12. Ballarino, A., HTS current leads for the LHC magnet powering system, Physica C (2002) 372-376 1413-1418
13. Lebrun, Ph., Cryogenics for the Large Hadron Collider, IEEE Trans. Appl. Superconductivity (2000) 10 1500-1508
14. Barranco-Luque, M. & Taviani, L., Gaseous helium storage and management in the cryogenic system for the LHC, ICEC18 Mumbai, Narosa Publishing (2000) 143-146

15. Wagner, U. & Claudet, S., Upgrade of four cryogenic helium refrigerators used in the LEP collider for LHC refrigeration, ICEC21 Prague, Icaris (2006) 39-42
16. Claudet, S., Gayet, Ph. & Wagner, U., Specification of four new large 4.5 K refrigerators for the LHC, Advances in Cryogenic Engineering (2000) 45B 1269-1276
17. Gruehagen, H. & Wagner, U., Measured performance of four new 18 kW@4.5 K helium refrigerators for the LHC cryogenic system, ICEC20 Beijing, Elsevier (2005) 991-994
18. Claudet, S., Gayet, Ph., Jager, B., Millet, F., Roussel, P., Tavian, L. & Wagner, U., Specification of eight 2400 W @ 1.8 K refrigeration units for the LHC, ICEC18 Mumbai, Narosa Publishing (2000) 207-210
19. Millet, F., Claudet, S. & Ferlin, G., Performance assessment of 35 cold hydrodynamic compressors for the 1.8 K refrigeration units of the LHC, Advances in Cryogenic Engineering, AIP823 (2005) 51B 1837-1844
20. Claudet, S., Ferlin, G., Millet, F. & Tavian, L., 1.8 K refrigeration units for the LHC: performance assessment of pre-series units, ICEC20 Beijing, Elsevier (2005) 999-1002
21. Gayet, Ph. & Sicard, C.H, Deployment and Integration of Industrial Controls : The Case of LHC Cryogenics Controls, ICALEPS9 Gyeongju, JACoW (2003) 463-465
22. Liu, L., Riddone, G., Serio, L. & Tavian, L., Cooldown of the first sector of the Large Hadron Collider: comparison between mathematical model and measurements, Advances in Cryogenic Engineering, AIP985 (2008) 53B 1395-1402
23. Millet, F. *et al.*, Commissioning the cryogenic system of the first LHC sector, Advances in Cryogenic Engineering, AIP985 (2008) 53B 1403-1410
24. Serio, L. *et al.*, Validation and performance of the LHC cryogenic system through commissioning of the first sector, Advances in Cryogenic Engineering, AIP985 (2008) 53B 1411-1418
25. Claudet, S., Lebrun, Ph., Tavian, L. & Wagner, U., Exergy analysis of the cryogenic helium distribution system for the Large Hadron Collider (LHC), Advances in Cryogenic Engineering, AIP1218 (2010) 55B 1267-1274
26. Ferlin, G., Claudet, S., Tavian, L. & Wagner, U., 1.9 K heat inleak and resistive heating measurements on LHC cryomagnets, Advances in Cryogenic Engineering, AIP1218 (2010) 55B 1275-1282
27. Maglioni, C., Parma, V., Poncet, A. & Serio, L., Experimental validation of the thermal performance of the 1.9 K magnet cryostats during the commissioning of the LHC, ICEC22 Seoul, KIAS (2009) 57-62
28. Claudet, S., Lebrun, Ph., Serio, L., Tavian, L., van Weelderden, R. & Wagner, U., Cryogenic heat load and refrigeration capacity management at the Large Hadron Collider (LHC), ICEC22 Seoul, KIAS (2009) 835-840
29. Vauthier, N. *et al.*, First experience with the LHC cryogenic instrumentation, Advances in Cryogenic Engineering, AIP985 (2008) 53B 957-964
30. Balle, Ch., Casas-Cubillos, J., Vauthier, N. and Thermeau, J.P, Calibration of cryogenic thermometers for the LHC, Advances in Cryogenic Engineering, AIP985 (2008) 53B 965-972
31. Perin, A. *et al.*, Commissioning of the cryogenics in the LHC long straight sections, Advances in Cryogenic Engineering, AIP1218 (2010) 55B 1309-1316
32. Darve, C. *et al.*, Commissioning and first operation of the low-beta triplets and their electrical feedboxes at the Large Hadron Collider, Advances in Cryogenic Engineering, AIP1218 (2010) 55B 1283-1290
33. Bajko, M. *et al.*, Report of the Task Force on the incident of 19 September 2008 at the LHC, CERN-LHC Project Report 1168 (2009)
34. Polinski, J. *et al.*, Risk analysis update of the LHC cryogenic system following the 19 September 2008 incident, paper presented at this conference
35. Brodzinski, K. *et al.*, The LHC cryogenic operation for first collisions and physics run, paper presented at this conference