CERN/EF/EHS-CC/76-16 17 December 1976

EUROPEAN HYBRID SPECTROMETER (EHS)

Definition of CERN Contribution to Part A

For the construction and installation of the European Hybrid Spectrometer (EHS) Part A, in EHN1 at CERN, CERN will assume the project coordination, will specify the equipment supplied externally and will contribute the infrastructure, equipment and services for completion and commissioning of the whole system.

The sharing of work and supplies between CERN and the contributing laboratories is defined in the following papers:

- sharing between CERN and Rutherford Laboratory (RL) for the bubble chamber RCBC in CERN/EF/EHS-CC/76-15
- sharing between CERN and CEA (Saclay) for the magnet Ml in CERN/EF/EHS-CC/76-14
- sharing between CERN and NIKHEF/Vienna for the drift chambers D1-D6 in CERN/EF/EHS-CC/77-18 and in CERN/EF/EHS-CC/77-19.

The CERN contribution to EHS, Part A, consists of services and supplies in the frame-work of general assistance to experiments in EHN1, in particular:

- installation of huts for operation, data acquisition and maintenance:


1 hut of 5 x 11 m_2^2 for 20 racks and control room 1 hut of 5 x 11 m_2^2 for 30 racks of detector electronics 1 hut of 4 x 11 m_2^2 for data acquisition 1 hut of 4 x 11 m_2^2 for maintenance and repair 1 hut of 4 x 10 m^2 for camera and film handling

- helium refrigeration for RCBC

- helium liquefaction for M1.

Furthermore, as part of the EHS budget, the following items will be provided by CERN:

- 1. Additional general installations in EHN1
- 2. Instrumentation and installation of RCBC
- 3. Instrumentation and installation of M1
- 4. Monitoring system, including computer
- 5. Data acquisition system, including computer



APPENDIX TO CERN/EF/EHS-CC/76-16

Detailed list of items provided by CERN to EHS, Part A

1. Additional general installations in EHN1 - internal equipment of five huts - rack structure, 50 x - battery backed 220 V/50 Hz supply (60kVA) - special tools for handling of equipment - alignment of equipment - switchboards, cable trays - resilient mounts of iron frame 2. Instrumentation and installation of RCBC - He transfer lines - Gas storage Warm tanks, 50 m³, 10 bar, stainless Battery stations Corblin compressor, 6 m³/h, 250 bar, including control panel Gas purifier Distribution panel and instrumentation Oil-free pump - Pipework Pump-outs Filling + purge lines Pump lines Compressed air lines Expansion system pipes Camera pipework - Vent lines Warm vents Cold vent Check valves Nitrogen purge - Cabling 220/380 V power Measurements and controls - Film handling hut (internal equipment) - Hydrogen safety Alarm system, 8 sensors, including electronics Expansion system enclosure Ventilated duct Hydrogen room, ventilated

.../...

3. Instrumentation and installation of Ml

- Cold equipment Transfer lines He dewar, 1000 1 Valve box, cold valves Cold safety valves
- Instrumentation
 Valves, actuators
 Solenoid v., converters
 Pressure transm., manometers
 Manual v., reducing v.
 Check v., safety v.
 Panel mounting, synoptics
- Vacuum Turbomolecular group Purge group (Roots p.) Pump-out group Valves Vacuum gauges, switches, etc.
- Power supply, discharge 4000 A connections Power supply, AC connect. Dump resistors Water purifier
- Pipework Pump-out lines, panel Purge lines, panel Warm He recovery Main pump line Air supply Cooling water Dump resistor water system
- Cabling Measurements and controls 220/380 V power
- Control room instrumentation Controlers Heaters
 Power supplies for sensors
 Alarms, interlocks
 Coil fault detection


.../...


- Test at Saclay

- Field map measurements

- 4. Monitoring system
 - NORD-10 type computer, 48k, 10 M disc
 - Computer terminals (2 printers, 2 VDU, 1 display terminal)
 - Monitoring RCBC, M1
 - Operating console, alarms, panels
 - CAMAC crate + interface to monitoring computer
 - Drift chamber monitoring
 - MWPC monitoring
 - Infrastructure for extension to Part B/C
- 5. Data acquisition system
 - NORD-10 type computer, 96k, 10 M disc, 2 tape units
 - Terminals (2 printers, 2 VDU, 1 display term., 1 printer/plotter)
 - CAMAC crate + interface to computer
 - Fast read-out from drift chambers (except DTR read-out controllers)
 - MWPC read-out, trigger logic commands
 - Infrastructure for extension to Part B/C
- 6. Construction and installation of multi-wire proportional chambers
 - W , W Chambers + electronics 4000 wires Small beam definition MWPC 400 wires

 - Supports, survey facilities
 - Gas station
- 7. Installation of drift chambers
 - Supports, survey facilities
 - Gas station
- 8. Modification and installation of magnet M2
 - Modification and installation of two RL magnets





	Slorage Aera		
• • •		 10 m	