


## Status of the LHCb Detector

On behalf of the LHCb Collaboration  
Frédéric Machefert

# Introduction

- **LHCb is the dedicated B physics experiment at the LHC devoted to the precision study of CP violation and rare decays**
- **The collaboration includes 48 institutes from 14 countries and more than 600 members**
- **The purpose of LHCb is**
  - Extend B physics results obtained in B-factories and the Tevatron
  - Search for new physics in a complementary way to ATLAS/CMS
- **LHCb will benefit from**
  - A large  $b\bar{b}$  cross-section in the forward region
    - At  $L=2 \times 10^{32}/\text{cm}^2\text{s}$ ,  $10^{12}$  B hadrons in  $10^7\text{s}$
  - B hadrons are both likely to be in the forward accept
  - B have a momentum  $\sim 50$  GeV
    - Good decay time resolution
    - Good background rejection



# The Infrastructures and the Beam Pipe


## ■ Cavern/Surface Infrastructures are almost finished

- Platforms, walls, balcony
- Gas extraction / distribution
- Cooling distribution for detectors is being done in parallel with detector installation
- Safety equipments are in operation
- Radiation measurements in operation
- Radiation Shield should be closed in September
- Still some work at the surface

## ■ Beam Pipe

- The four sections (3 in Beryllium and the last one in Z in stainless steel) are
  - Installed, interconnected, pumped down and baked out
- Is now filled of neon (back to atmospheric pressure) to preserve the quality of the tube after bake out

# The LHCb detector



# The Tracking System : Magnet and VELO


## ■ The LHCb magnet

- is installed since 2004
- Has reached its nominal field in November'04



## ■ The Vertex locator

- is made of 21 stations (Silicon modules)
  - R and  $\phi$  layers each
  - Strip pitch from 40 to 100 $\mu$ m
- Two retractable halves for injection
- Approach the beam down to 8mm
- Cabling of the detector is well advanced
- Cooling system is about to be installed and commissioned
- Movement tests have been done and show a good positioning reproducibility
- Left/Right side have electronically tested
- TFC and DAQ are installed
- Next main step is to perform a DAQ acquisition of a slice of the detector using the full data path




# The Tracking System : Trigger and Inner Trackers

- Apart from the vertex locator (VELO), LHCb has three main tracking detectors


- **The Trigger Tracker**

- 2 double layers
  - 1 layer with stereo strips
- Silicon microstrip sensors
  - ~200 $\mu$ m readout pitch
- Sensor module production is finished
- Installation is in progress
- Cabling and cooling well advanced




- **Inner tracker**

- 4 layer Silicon detector
- Inner region of the T1, T2 and T3 chambers
  - 2% of the area
  - 20% of the tracks
- Work on services is going on
  - Cables, cooling
- Will be followed by final box installation




# Outer Tracker

- 4 double layers
  - Kapton and Aluminium Straws






- The modules and the frames have been installed
- Front-end electronics is being installed in the frames
- Services are installed
- Cooling has been commissioned
- Final gas system will be commissioned in August or September
  
- Entire and final readout chain has been tested on a farm node

See presentation by H. Terrier on Thursday 19th



# RICH1 and RICH2

- Cerenkov detectors based on the HPD technology
  - 3 medium for good  $K/\pi$  separation up to 100GeV



- All the HPDs have been delivered and qualified
- RICH 1
  - structure has been tested (leak)
  - Mirror alignment is underway
- RICH 2
  - In the commissioning phase (all columns/boxes installed)
  - Readout performed with pulsed

See presentation by U. Kerzel on Friday 20th



# The Calorimeter System


- The calorimeter system is made of 4 sub-detectors
  - SPD/PRS (Pb/Scintillator)
  - ECAL/HCAL
    - Pb/Scintillator shashlik and Fe/Scintillator tiles




- All the modules have been installed
- Front-end is being installed/tested
  - Mostly done for ECAL/HCAL
- Cabling and cooling well advanced
- Commissioning phase started




# Muon System : Chamber Status



- **1368 MWPCs**
  - M2-M5 chambers (4 detection layers) and outer M1 (2 layers) region
- **24 3-GEMs**
  - In the central region of M1




- 3-GEM detector parts are ready
  - Chamber dressing is done
  - Installation planned in Autumn
- M2-M5 chambers mostly installed, tested and pre-aligned
- M1 chamber was a bit delayed
  - Work should be completed by March 2008




# Commissioning Strategy

- **Commissioning started this year**
  - each detector independently
    - Was done in parallel
  - Controls
  - Safety
  - Front-end to DAQ
  - Calibration systems
- **Use of cosmics is envisaged**
  - LHCb geometry is not adequate
  - Still we may think of
    - Tuning the relative timing between
      - ECAL/SPD/PRS/HCAL
      - Tracking (T1-T1-T2)
      - Muon chambers
- **Particles are required to complete the commissioning of the detector**




# HCAL/ECAL/L0Trigger Commissioning Test



# Commissioning : up to the event display

## HCAL



# Time and Space alignment with Beam

- **Reasonable initial delay will be defined**
  - during commissioning tests (using test pulses for most of the detectors)
    - We may expect an accuracy of a few ns
  - But we also need to correlate the sub-detectors
  
- **HCAL as the first trigger system**
  - The L0 trigger will select any event with activity in the HCAL
  - The TFC system will be in a specific mode
    - Acquisition of 5 consecutive events, 2 before and 2 after
  - Delays have to be adjusted to minimize the amount of spill-over/optimize the signal
  
- **Tracking is the first element to be aligned with beam**
  - Tracking system position is surveyed
    - Alignment is measured at the  $\sim 0.5\text{mm}$  level ( $\sim 0.3\text{mm}$  for VELO box)
      - Particles will be used to improve the knowledge on the position of the detectors
  
- **The first collisions will be done without magnetic field**
  - Energy is obtained from the calorimeter
  
- **Calorimeter and muon have been positioned (installation) with  $\sim 1\text{mm}$  precision**
  - Use electrons and hadrons for calorimeters and muons for muon system


# Momentum and Energy Calibration

## ■ Momentum

- Momentum resolution sensitive to B-field inhomogeneities/misalignment
  - Field map for both polarities has been measured in 2005
    - Uncertainty < 0.03% (negligible effect on the momentum)

## ■ B-field polarity will be regularly flipped during data taking

- Reproducibility within measurement accuracy
- Mass resolution will give a cross-check :  $K_S, J/\psi$



## ■ ECAL energy


- Cosmics allowed to reach 10% calibration
- Energy flow methods should provide a few %
- Iterative methods being developed to reach better than 1% level
  - Resolved  $\pi^0$  mass reconstruction (calibration runs of O(10 minutes) for all areas)

# Physics Preparation : First Data

- $J/\psi$  production
- $\sin(2\beta)$  with  $B^0 \rightarrow J/\psi K_s$
- $\phi_s$  and  $\Delta\Gamma_s$  with  $B_s \rightarrow J/\psi \phi$
- $B_s \rightarrow \mu\mu$ 
  - SM Branching ratio may be highly enhanced (SUSY) :  $BR(SM) \sim 3.5 \times 10^{-9}$
  - LHCb should be able to set limits down to  $1 \times 10^{-8}$  with less than  $0.2 \text{ fb}^{-1}$

See presentation by  
S. Eisenhardt  
Friday 20th

LHCb Sensitivity (*signal+bkg is observed*)



With  $L=2\text{fb}^{-1}$

$3\sigma$  observation if at SM value



# Conclusion

- **Installation of detectors, services and DAQ system are getting close to completion**
- **Detector commissioning is ongoing**
  - Either in parallel with commissioning dedicated systems
  - Or using the full LHCb ECS/DAQ standard systems at the pit
- **LHCb will be ready**
  - To collect data with its full detector at LHC start-up in 2008
  - To exploit the large B meson cross-section at LHC
- **LHCb will be ready to discover new physics signals !**
  - With an excellent mass, decay-time resolution and particle identification
  - With a flexible and robust trigger dedicated to B physics

# Backup Slides

# Outer Tracker Aging

- Problem was a gain loss in the neighbourhood of the irradiation point
  - This was in fact NOT due to the accumulated dose
  - Out gassing of the Araldite



## Beneficial effects:

- Flushing
- HV Training
- Heating



Gas flow

In situ heating procedure of the modules is under study